

SPECIFICATION CHANGE NO.	19
--------------------------	----

MILITARY SEA TRANSPORTATION SERVICE, PACIFIC
N.S.C.
OAKLAND, CALIFORNIA 94625

DATE OF ORIGIN
15 September 1969

SHIP USNS POPE (T-AP 110)	CONTRACTOR Triple "A" Machine Shop
SPECIFICATION NO. MSTSP 70-11	SPECIFIC ITEM NO. 303
ITEM NO. BOILER BRICK WORK: (SM)	ADDENDUM NO. 1

DESCRIPTION OF WORK

Accomplish the following repairs as required by USCG.

3 Boiler:

Renew slope in soot box area.

#3 & #4 Boiler:

Renew tile between soot box door and drum front 4' X 2'.

#4 Boiler:

Renew the castable refractory on rear wall between super heater and generator tubes approximately 1' X 2'.

Renew refractory in way of front lower door sill size $2\frac{1}{2}'$ X 1'

#1 Boiler

Renew castable above roof tube. Remove casing for pouring and replace same.

RECEIVED
OCT 1 1969

USNS POPE T-AP110

jmb

12ND MSTSPAC FORM 4330/12 (REV. 12-68)

POPE