


Max



0  
5  
10  
15  
20  
25

Nautical Miles

SCALE 1:250,000

# AIR FACILITIES DATA PAMPHLET

## LAOS



## MAY

## 1969

FLIGHT INFORMATION  
CENTER  
VIENTIANE

No. → L08

Ground signal → Vientiane/LT/V

TE 4388 ← UTM Grid Coordinates

Map Reference → 1:250,000 & 1:500,000 → NE 48-9, J-11D

Elevation → Elev 561

Facilities If available → ( Tower: )  
( Comm: )  
( Nav aids: )  
( Remarks: )  
Operational Status

6538x150 Concrete

17-59N, 102-34E ← Geographic Coordinates

13/31 ← Runway Orientation

← Runway Composition

← Runway Length & Width

OPEN: Open to all Company Aircraft unless otherwise stated.

RESTRICTED: Restrictions are noted for specific aircraft. Smaller aircraft than those noted are Unrestricted.

CLOSED: Closed to all fixed wing aircraft

UNF: Unfriendly


CONTENTS

SECTION I	Area Approach and Letdown Plates
SECTION II	Lima Airfields STOL Sites
SECTION III	Airfield Index by UTM Grid Coordinates
SECTION IV	Alphabetical Index
SECTION V	General Information

# DELTA AIRWAY

OFF DELTA AIRWAY  
ALL ROUTES

AIRWAY ALTITUDES  
North - Odd  
South - Even



altitudes set 29.92 upon passing 4000'  
altitude. Airway extends from surface  
to 300' PA.


Aircraft inbound to L08 from the  
north will avoid outbound Delta airway.  
20 nm away from centerline until  
heading of 140° (AC west) or 270°  
(AC east) is received.

Departure North - Runway 31  
Maintain runway heading till  
15 nm then 1/2 SRT left to south  
heading overhead L08 NDB  
between 2500' and 3000' then  
climb on course centerline.

Aircraft will guard VHF 118.1  
in 15 nm of the airport.


Aircraft below 3000' MSL and 15 nm of L08  
will proceed directly to the airport.

**Departure North - Runway 13**  
Maintain runway heading till  
1000' then 1/2 SRT right to south  
continuing overhead L08 NDB  
between 2500' and 3000' then  
climb on course centerline.




## Approach Chart

Pakse, Laos



Day & Night minima  
1300' 1 mile


Missed Approach: Immediate right turn,  
climb on 325° to 3000' then right turn  
and home on station.




Approach Chart

Tower 118.1 236.6  
 Company Operated Facilities  
 H/F 8765 kcs.  
 VHF 119.1, 121.5

VIENTIANE  
 VTN 400 kHz  
 AM 1580 kcs



**Missed Approach**  
 Climb out on 360°  
 executing a right  
 climbing turn with-  
 in 10 NM Track  
 inbound on 200°  
 to recross VTN at  
 3000' or higher.




R/W Elev	560'	R/W Hdq	13/31
Var.	0°	R/W Length	6538'
QFE	500'-1	R/W Sfc	Concrete
QNH	1061'		

17° 59' N - 102° 34' E

Approach Chart


Tower: 118.1  
 Company Operated Facilities:  
 H/F 8765, 5568 kcs. APN-2  
 VHF 119.1, 121.5

LUANG PRABANG  
 LP 379 kcs.



**Missed Approach**

Climb on 255° for 1 1/2  
 minutes, left turn &  
 home on LP 379 kcs.




R/W Elev	997'	R/W Hdq.	06/24
Var.	0°	R/W Length	5413
QFE	5000'-2	R/W Sfc.	Macadam
QNH	5997'		

19° 54' N - 102° 09' E

Approach Chart


Savannakhet, Laos  
LIMA-39

Tower 118.1, 236.6



Day and Night minima - 500', 1 mile  
Missed Approach: left turn, climb on 110° to 3500'; return overhead station.


CAUTION: Do not cross Mekong River (See Thailand Prohibited area)




NDB (ADF)-1 RWY12

302  
AL-1525 (USAF)

UDORN A  
CHANGWAT UDORN THANI, THAILA



Procedure turn South side of course remain within 10NM



ELEV 583

CATEGORY	A	B	C	D
S-12	1120-1	537	(600-1)	
CIRCLING	1120-1	537	(600-1) 1140-1½ 557 (600-1½)	1140-2 557 (600-2)

NOTE: U.S. aircraft are restricted from flying within a 25 NM radius of VIENTIANE.

CAUTION: Construction REIL oval Rwy 30

NDB (ADF)-1 RWY12

17°22'N-102°48'E

CHANGWAT UDORN THANI, THAILA  
UDORN A

LIMA AIRFIELDS

L01 Moug Sung TH 3348  
 NF 48-13, J-11A 20-19N, 102-27E  
 Elev 3281 1300x80 03/21  
CLOSED GROWN OVER

L02 Moug Ou Tay QE 8948  
 NE47-8, J-10B 22-07N, 101-48E  
 Elev 2297 3000x118 04/22  
CLOSED UNF

L03 Xieng Khong Ville UG 2740  
 NE48-1, J11D 19-21N, 103-22E  
 Elev 3117 2550x40 06/24  
CLOSED - UNF

L04 Sam Neua VH 0358  
 NF48-14, J-11A 20-25N, 104-04E  
 Elev 3281 3445x40 09/27  
CLOSED UNF

L05 Paksong XB 4394  
 ND48-3, K-10A 15-19N, 106-20E  
 Elev 3445 3280x70 18/36  
CLOSED GROWN OVER

L06 Ken Thao QV 5364  
 NE47-12, J-10C 17-45N, 101-23N  
 Elev 875 2720x132 Sod/Laterite 09/27  
 Land 27 TO 09, closed to large acft. during  
 rainy season. Caution when wet.  
RESTRICTED  
C123 MAXLW 52. MAXTOW 48.  
C123K MAXLW 52. MAXTOW 48.

L07 Khong Island WA 8960  
 ND48-7, K-10A 14-07N, 105-50E  
 Elev 250 3110x62 Gravel 03/21  
 Closed to large aircraft during rainy season.  
RESTRICTED  
C123 MAXLW 52. MAXTOW 48.  
C123K MAXLW 52. MAXTOW 48.

L08 Vientiane TE 4388  
 NE48-9, J-11D 17-59N, 102-34E  
 Elev 561 6538x150 Concrete 13/31  
 Lights: Until 2100L, avail. later on request.  
 Fuel: 115/145, JP-1  
 Tower: 118.1 236.6 daylight hours  
 Company radio: VHF 119.1, 118.1, 121.5  
 HF 5568, 8765  
 Navaids: NDB 400 VTN  
OPEN

L09 Paklay QA 5516  
 NE48-8, J-10C 18-13N, 101-25E  
 Elev 917 1824x110 Grass 02/20  
RESTRICTED  
Caribou Closed when wet. MAXTOW 26.  
MAX XWIND 10kts.

L10 Attopeu/VV XB 9738  
 ND48-8, K10A 14-48N, 106-50E  
 Elev 344 4400x37 Laterite 13/31  
CLOSED UNF Activity

L11 Pakse WB 8473  
 ND48-7, K-10A 15-08N, 105-47E  
 Elev 400 5325x130 Asphalt 14/32  
 Fuel: 115/145, JP-1  
 Tower: 118.1 daylight hours  
 Company Radio: VHF 119.1, 118.1, 121.5  
 HF 5568, 8765  
 Navaids: NDB 240 PS  
OPEN

13 Moug Het UJ 9803  
 NF48-14, J-11A 20-50N, 104-02E  
 Elev 886 5000x80 09/27  
CLOSED UNF

---

L15 Phong Saly TK 0000  
 NF48-9, J11A 21-41N, 102-06E  
 Elev 4500 990x50 01/19  
CLOSED UNF

---

L16 Vang Vieng TF 3294  
 NE48-5, J-11D 18-55N, 102-28E  
 Elev 971 4922 x90 Laterite/stone 18/36  
RESTRICTED  
 C46 MAXTOW 45.  
 C123 MAXTOW 52.

---

L17 Sop Hao VH 4373  
 NF48-14, J-11A 20-33N, 104-27E  
 Elev 820 1380x100 03/21  
CLOSED UNF

---

L19 Moug Nong XD 6010  
 NE48-7, J-11D 16-22N, 106-30E  
 Elev 600 1480x  
CLOSED UNF

---

L20 Bun Taio (Buntai) RD 0968  
 NF47-12, J-10B 21-06N, 101-59E  
 Elev 1772 1300x60 18/36  
CLOSED UNF

---

L21 Phong Savan UG 1253  
 NE48-1, J-11D 19-28N, 103-13E  
 Elev 3609 2950x164 15/33  
CLOSED UNF

L22 Xieng Khouang UG 0552  
 NE48-1, J-11D 19-27N, 103-09E  
 Elev 3444 5250x140 06/24  
CLOSED UNF

---

L23 Sayaboury QB 8630  
 NE47-4, J-10C 19-51N, 101-43E  
 Elev 1070 2670x62 Gravel 16/34  
 Tower: 118.1  
 Nav aids: NDB 365 SB  
 Land 16 TO 16, Do not taxi off runway or improved  
 parking area during rainy season.  
RESTRICTED  
 C123 MAXLW 52. MAXTOW 48.  
 C123K MAXLW 55. MAXTOW 55.

---

L25 Ban Houei Sai/TT PC 5141  
 NF47-15, J-10B 20-15N, 100-25E  
 Elev 1380 4920x118 Laterite 16/34  
 Fuel: 115/145, JP-1  
 Company Radio: VHF 119.1, 118.1, 121.5  
 HF 5568, 8765  
 Nav aids: NDB 340 RK, daylight hours  
OPEN

---

L26 Ou Neua QE 8869  
 NF47-8, J-10B 22-18N, 101-48E  
 Elev 2592 2890x200 16/34  
CLOSED UNF

---

L27 Moug Sai RC 1290  
 NF47-12, J-11B 20-41N, 102-00E  
 Elev 1804 3770x50 03/21  
CLOSED UNF

---

L30 Boun Neua (Old) RD 0097  
 NF47-12, J-10B 21-38N, 101-54E  
 Elev 3035 1900x80 05/23  
CLOSED UNF

L31 Moug Peun UH 8235

NF48-14, J-11A 20-12N, 103-53E  
Elev 3937 1410x50 16/34  
CLOSED UNF

L34 Moug Houn QC 5729

NF47-16, J-10B 20-08N, 101-27E  
Elev 1600 2130x70 03/21  
CLOSED UNF

L35 Paksane UF 5934

NE48-6, J-11D 18-24N, 103-40E  
Elev 515 4650/75 Laterite/Sod 18/36  
Braking action Fair to Good when wet. Do not  
taxi off runway during rainy season.  
OPEN

L38 Tchepone XD 2748

NE48-15, J-11D 16-43N, 106-12E  
Elev 558 3940x65  
CLOSED UNF

L39 Savannakhet VD 7530

NE 48-14, 11D 16-33N, 104-46E  
Elev 509 5850x140 Asphalt 04/22  
Lights: Available on request  
Fuel: 115/145, JP-1  
Tower: 118.1  
Company radio: VHF 119.1, 118.1, 121.5  
HF 5568, 8765  
Nav aids: NDB 290 SV  
OPEN

L40 Thakhek - East VE 8521

NE 48-10, J-11D 17-23N, 104-52E  
Elev 500 2660x100 Sod 10/28  
CLOSED

L40A Thakhek - West VE 8124

NE48-10, J-11D 17-24N, 104-49E  
Elev 492 2705x100 Crushed Rock 10/28  
Fuel: 115/145

Do not taxi off runway or improved parking area  
on South side of runway at West end when wet.

RESTRICTED

C123 MAXLW 52.5 MAXTOW 48.

C123K MAXLW 52.5 MAXTOW 48.

L41 Ban Khoang (Moug Hai) QD 9232

NF47-12, J-10B 21-04N, 101-49E  
Elev 2789 2030x100 13/31  
CLOSED UNF

L42 Moug Sing QD 2343

NF47-12, J-10B 21-10N, 101-09E  
Elev 2231 3960x164 13/31  
CLOSED UNF

L44 Saravane XC 5237

ND48-3, K-10A 15-41N, 106-25E  
Elev 550 4796x60 Laterite 06/24  
RESTRICTED

C123 MAXTOW 52. Normally closed during  
rainy season.

L45 Ban Soukhouma WB 8518

ND48-7, K-10A 14-38N, 105-48E  
Elev 252 2950x  
CLOSED

L46 Seno WD 0143

NE48-15, J-11D 16-40N, 105-01E  
Elev 607 5960x131 PSP/Asphalt 08/26  
3937x131 Laterite/Asphalt 04/22

RESTRICTED

C123 Use Runway 04/22, MAXTOW 51.

L47 Xam Tai VH 6211  
 NE48-2, J-11D 20-00N, 104-38E  
 Elev 820 1970x70 11/29  
CLOSED UNF

---

L49 Sanakhan QV 8683  
 NE47-12, J-10C 17-55N, 101-36E  
 Elev 900 1800x70 Dirt 05/23  
OPEN  
Caribou, Helio, Porter only.

---

L50 Ban Na Tai TH 6291  
 NF48-13, J-11A 20-42N, 102-43E  
 Elev 1470x130 08/26  
CLOSED UNF

---

L52 Nong Khang VH 0581  
 NF 48-14, J-11A 20-37N, 104-05E  
 Elev 3491 1600x250 07/25  
CLOSED UNF

---

L53 Ban Phan Hop WE 7941  
 NE48-11, J-11D 17-32N, 105-45E  
 Elev 558 2760x40 16/34  
CLOSED UNF

---

L54 Luang Prabang TH 0302  
 NE48-1, J-11D 19-54N, 102-10E  
 Elev 997 5413x93 Asphalt 06/24  
 Tower: 118.1 236.6 daylight hours  
 Company Radio: VHF 119.1, 118.1, 121.5  
 HF 5568, 8765  
 Nav aids: NDB 379 LP  
OPEN

L56 Houei Kong/X XB 6473  
 ND48-4, K-10A 15-08N, 106-32E  
 Elev 2930 1800x80 07/25  
OPEN  
Helio, Porter only

---

L57 Mahaxay WE 2125  
 NE48-11, J-11D 17-25N, 105-12E  
 Elev 498 1200x  
CLOSED UNF

---

L59 Moug Son/U UH 2862  
 NF48-13, J-11A 20-27N, 103-21E  
 Elev 2350 1970x50 Gravel 16/34  
 1350' of runway useable  
CLOSED UNF

---

L60 Moug Soi VH 5040  
 NF48-14, J-11A 20-16N, 104-31E  
 Elev 1312 2000x65 09/27  
CLOSED UNF

---

L61 Moug Pha Lane WD 5844  
 NE48-15, J-11D 16-41N, 105-33E  
 Elev 520 1550x75 Sand/Sod 06/25  
CLOSED

---

L100 Nam Tha QD 5019  
 NF 47-16, J-10B 20-58N, 101-24E  
 Elev 1968 4600x80 18/36  
CLOSED UNF

L105 Ban Than Lay WE 0711

NE48-11, J-11D 17-17N, 105-04E  
Elev 500 1800x50 15/33  
CLOSED UNF

L106 Moug Phanh TG 9651

NE48-1, J-11D 19-26N, 103-05E  
Elev 3400 3500x120 09/27  
CLOSED UNF

L107 Wat Phu WB 9142

ND48-7, K-10A 14-07N, 105-50E  
Elev 400 2954x160 Earth 06/24  
Normally closed during rainy season.  
RESTRICTED  
C123 MAXTOW 48.  
C123K MAXLW 54. MAXTOW 52.5

L108 Moug Soui TG 7960

NF48-13, J-11D 19-32N, 102-54E  
Elev 3600 5600x110 Laterite 06/24  
Fuel: 115/145  
Land 24 TO 06  
RESTRICTED  
C-46 MAXTOW 46. Closed when wet.  
C123 MAXTOW 51. Closed when wet.

L109 Moug Kheung UG 0272

NF48-13, J-11D 19-38N, 103-06E  
Elev 3500 5200x100 03/21  
CLOSED UNF

L110 Ban An TG 9464

NF48-13, J-11D 19-35N, 103-02E  
Elev 3700 3300x75 04/22  
CLOSED UNF

STOL SITES

LS1 Moug Ngai/N VG 0212

NE48-2, J-11D 19-07N, 104-05E  
Elev 4500 1313x98 Grass 12/30  
Land 12 TO 30, Medium Upslope  
CLOSED UNF

LS2 San Tiau/T UG 5055

NE48-2, J-11D 19-29N, 103-35E  
Elev 5000 738x70 Grass 11/29  
Land 29 TO 11, Rolling Steep Upslope  
RESTRICTED  
Helio, Porter Newly checked out pilots.

LS3 Nong Het UG 9456

NE48-2, J-11D 19-30N, 103-59E  
Elev 4500 2500x70 10/28  
CLOSED UNF

LS4 Kiou Cacham TG 0968

NE48-1, J-11D 19-35N, 102-13E  
Elev 4400 900x50 Dirt 18/36  
OPEN  
Helio, Porter only

LS5 Pa Doung/I UG 0212

NE48-1, J-11D 19-06N, 103-07E  
Elev 4500 2100x275 01/19  
Land 19 TO 01  
RESTRICTED  
Caribou Closed when wet. MAXTOW (Dry) 28,  
(Wet) 26. MAX XWIND 10 kts.

LS6 Phou Vieng/U UG 0789

NE48-1, J-11D 19-48N, 103-10E  
Elev 3300 760x66 02/20  
Land 19 TO 01 Rolling Level  
RESTRICTED  
Helio, Porter Newly checked out pilots.

---

LS7 Nam Lan UG 5585

NE48-1, J-11D 19-45N, 103-37E  
Elev 4000 650x150 01/19  
CLOSED UNF

---

LS8 Khang Khai UG 1758

NE48-1, J-11D 19-31N, 103-15E  
Elev 4300 800x50 09/27  
CLOSED UNF

---

LS9 Lat Houang UG 0945

NE48-1, J-11D 19-24N, 103-11E  
Elev 3900 3000x400 03/21  
CLOSED UNF

---

LS10 Ban Ban UG 4971

NE48-2, J-11D 19-38N, 103-34E  
Elev 1888 1250x80 14/32  
CLOSED UNF

---

LS11 Tha Thom UG 5300

NE48-2, J-11D 19-38N, 103-34E  
Elev 850 1250x80 13/31  
CLOSED UNF

LS12 Ban Bonong UG 5684

NE48-10, J-11D 17-57N, 104-35E  
Elev 650 1200x150 14/32  
CLOSED

---

LS13 Ta Viang UG 3204

NE48-5, J-11D 19-02N, 103-24E  
Elev 1300 600x60 10/28  
CLOSED UNF

---

LS14 Pha Khao/T TG 9107

NE48-1, J-11D 19-03N, 103-01E  
Elev 3800 1700x200 Sod 09/27  
Land 09 TO 27  
RESTRICTED  
Caribou Newly checked out pilots. Closed when  
wet, MAXLW (dry) 26. MAXTOW 24.  
MAX XWIND 10 kts.

---

*30° dogleg*

LS15 Ban Na/IL TG 8536

NE48-1, J-11D 19-18N, 102-57E  
Elev 4600 1188x50 Dirt/Sod 17/35  
Land 35 TO 17, Rolling Steep Upslope  
OPEN

Helio, Porter only.

LS16 Phou Fa/E "E" TG 7175

NE48-1, J-11D 19-40N, 102-49E  
Elev 5400 700x35 Dirt 07/25  
Land 25 TO 07  
CLOSED

LS17 Nam Chong/AN TG 6341  
 NE48-1, J-11D 19-21N, 102-45E  
 Elev 3900 800x45 Clay 16/34  
 Land 16 TO 34 Rolling Level  
RESTRICTED  
Helio, Porter when wet and/or for newly checked  
 out pilots.

-----

LS18 Tha Lin Noi UG 3451  
 NE48-1, J-11D 19-27N, 103-25E  
 Elev 4300 700x44 Dirt 11/29  
CLOSED UNF

-----

LS19 Phou Khe UG 1937  
 NE48-1, J-11D 19-19N, 103-17E  
 Elev 6200 400x25 Steep Upslope 18/36  
CLOSED UNF

-----

LS20 Sam Thong/P TG 7924  
 NE48-1, J-11D 19-12N, 102-54E  
 Elev 3800 2128/81 Laterite 14/32  
 Fuel: 115/145, JP-1  
 Land 32 TO 14, Rolling Steep Upslope  
RESTRICTED  
Caribou Caution when wet. MAXTOW 27.  
 C123 MAXLW 52. MAXTOW 43. MAX XWIND 5 kts.  
 MAX WIND at any time 10 kts.  
 C123K MAXLW 52. MAXTOW 48.

-----

LS21 Pha Peung UG 3822  
 NE48-1, J-11D 19-10N, 103-27E  
 Elev 5600 600x38 Clay 06/24  
 Land 06 TO 24, Steep Upslope  
CLOSED

LS22 Moug Oum/I UF 1796  
 NE48-5, J-11D 18-57N, 103-15E  
 Elev 3000 1030x62 Sod 05/32  
 Land 23 TO 05, Medium Upslope  
RESTRICTED  
Caribou Newly Checked out pilots.  
 Closed when wet. MAXLW 26. MAXTOW 24.  
 MAX XWIND 10 kts.  
 EMERGENCY USE ONLY

-----

LS23 Houei Sa An UG 3993  
 NE48-1, J-11D 19-50N, 103-28E  
 Elev 4100 700x60 06/24  
CLOSED GROWN OVER  
 UNF

-----

LS24 Moug Sam VG 2207  
 NE48-2, J-11D 19-03N, 104-16E  
 Elev 1300 1200x90 Dirt 15/33  
CLOSED GROWN OVER

-----

LS25 Phou Chai/PJ SG 9950  
 NE48-1, J-11D 19-25N, 102-08E  
 Elev 5200 2030x60 Sod 12/30  
 Land Optional TO 30  
RESTRICTED  
Caribou Newly checked out pilots. Closed when wet.  
 Go around critical.  
 MAXLW 28. MAXTOW 24. MAX XWIND 10 kts.

-----

LS26 Xieng Dat/U TG 6049  
 NE48-1, J-11D 19-25N, 102-43E  
 Elev 2500 3000x60 Dirt 17/35  
RESTRICTED  
 C123 Closed when wet. MAXLW 54. MAXTOW 54.  
 UNF

LS27 Houei Thom/TN UH 5312  
NE48-2, J-11D 20-00N, 103-36E  
Elev 4300 600x30 Dirt 18/36  
Land 18 TO 36  
CLOSED

UNF

LS28 Ban Done/T VF 2270  
NE48-6, J-11D 18-43N, 104-16E  
Elev 1000 1600x100 Dirt/Sod 17/35  
RESTRICTED  
Caribou MAXLW 28. MAXTOW 28(Dry) 26(Wet).  
MAX XWIND 10 kts. Closed when wet.

LS29 Ban Song UG 6791  
NE48-2, J-11D 19-49N, 103-44E  
Elev 4300 560x22 09/27  
CLOSED UNF

LS30 Long Tieng TG 8214  
NE48-1, J-11D 19-07N, 102-55E  
Elev 3120 2200x100 Laterite 14/32  
Fuel: 115/145, JP-1  
Large aircraft Land 32 TO 14.  
Medium Upslope. Large acft. 10 kts. XWIND.  
RESTRICTED  
C123 MAXTOW 48.  
C46 MAXTOW 44.

LS31 Pien Lieu UG 7393  
NE48-2, J-11D 19-50N, 103-48E  
Elev 4000 550x30 10/19  
CLOSED GROWN OVER

LS32 Bouam Long/U UG 2686  
NE48-1, J-11D 19-45N, 103-20E  
Elev 4800 1300x75 Clay 14/32  
Land 14 TO 32  
OPEN  
Helio, Porter only  
*Soft spot 200' from end runway 14*

LS33 San Pa Ka/T UH 0709  
NE48-1, J-11D 19-58N, 103-09E  
Elev 4300 750x50 Laterite 14/32  
Land 32 TO 14, Medium Upslope  
CLOSED  
*Friendly*

LS34 Ban Bouac UG 5932  
NE48-2, J-11D 19-17N, 103-40E  
Elev 4400 800x50 10/28  
CLOSED UNF

LS35 Kha Phu UG 4227  
NE48-1, J-11D 19-11N, 103-30E  
Elev 6100 650x40  
CLOSED GROWN OVER

LS36 Na Khang/LI UH 4110  
NE48-1, J-11D 19-59N, 103-29E  
Elev 4400 2265x130 Laterite 03/21  
Fuel: 115/145, JP-1  
Nav aids: NDB 1620 Beeper  
Land 03 TO 21, Rolling Medium Upslope  
CLOSED UNF

LS37 Moug Phun/II TG 6114

NE48-1, J-11D 19-06N, 102-43E  
Elev 3600 1485x70 Dirt/Sod 09/27  
Land optional TO 09  
OPEN  
Helio, Porter only

---

LS38 Houei Ki Nin/KY TG 8247

NE48-1, J-11D 19-24N, 102-55E  
Elev 3300 1000x60 Dirt/Clay 11/29  
Land 29 TO 11, Rolling Medium Upslope  
OPEN  
Helio, Porter only

UNF

---

LS39 Ban Khami UH 7723

NF48-14, J-11D 20-06N, 103-50E  
Elev 550x50 04/22  
CLOSED UNF

---

LS40 Ban Pha Ka/A UG 4747

NE48-2, J-11D 19-25N, 103-33E  
Elev 4300 850x50 Dirt 10/28  
Land 28 TO 10  
RESTRICTED  
Helio, Porter UNF Newly checked out pilots.

---

LS41 San Louang/LA TG 7149

NE48-1, J-11D 19-26N, 102-49E  
Elev 2700 700x40 Dirt/Clay 05/23  
Land 05 TO optional  
RESTRICTED  
Helio, Porter Newly Checked out pilots.

LS42 Phou Kong/I QB 4849

NE47-4, J-10C 19-26N, 101-20E  
Elev 4400 1300x50 Grass/Dirt 03/21  
Land 03 TO 21, Medium Upslope  
RESTRICTED  
Caribou Newly checked out pilots.  
Closed when wet. MAXLW 26. MAXTOW 24.  
MAX XWIND 10 kts.

---

LS43 Nape WF 0923

NE48-7, J-11D 18-18N, 105-05E  
Elev 1700 1480x130 08/26  
CLOSED UNF

---

LS44 Ban Keun TF 4431

NE48-5, J-11D 18-21N, 102-35E  
Elev 600 5000x40 Laterite 16/34  
Narrow airstrip, 100' trees bordering SE end of  
runway.  
C46 and C123 Land 16 TO 16.  
OPEN

---

LS45 Cang Sa Ni/V VF 1989

NE48-6, J-11D 18-53N, 104-14E  
Elev 1200 800x125 Dirt 15/33  
TO 15  
RESTRICTED  
Helio, Porter Newly checked out pilots.

---

LS46 Moug Moc/F UF 9591

NE48-6, J-11D 18-55N, 104-00E  
Elev 2900 1200x100 Clay/Sod 18/36  
Land 36 TO 18, Rolling Medium Upslope  
RESTRICTED  
Caribou Newly checked out pilots. Closed when wet.  
MAXLW 27. MAXTOW 24. MAX XWIND 10 kts.

LS47 Nam Thom VG 1417

NE48-2, J-11D 19-09N, 104-11E  
Elev 4800 645x50 15/33  
CLOSED

LS48 Chong Ha/NB/L UH 2817

NF48-13, J-11A 20-08N, 103-21E  
Elev 2100 1370x85 Grass 01/19  
CLOSED UNF

LS48A Moug Hiem/A UH 3020

NF48-13, J-11A 20-09N, 103-23E  
Elev 2150 2010x90 Sod 18/36  
Dikes at both ends of runway.  
CLOSED UNF

LS49 Lak Sao VF 9811

NE48-6, J-11D 18-11N, 104-59E  
Elev 1700 2950x115 18/36  
CLOSED UNF

LS50 Phu Cum/ II UH 0301

NE48-1, J-11D 19-54N, 103-07E  
Elev 4300 700x75 17/35

*Restricted Helio & porter*

CLOSED

LS50A Phu Cum/ II UH 0400

NE48-1, J-11D 19-54N, 103-07E  
Elev 3800 1600x67 13/31  
Land 31 TO 13, Medium Upslope  
OPEN  
Helio, Porter only.

LS51 Pa Ka/H TG 6317

NE48-1, J-11D 19-06N, 102-44E  
Elev 3500 800x60 Dirt 05/23  
Land 05 TO 23  
CLOSED

LS52 Ban Tha UG 5283

NE48-2, J-11D 19-45N, 103-35E  
Elev 3800 735x65 17/35  
CLOSED UNF

LS53 Ritaville TF 6634

NE48-5, J-11D 18-23N, 102-47E  
Elev 2400 3000x150 Dirt 08/26  
OPEN  
6123, Caribou, Helio, Porter. Closed when wet.

LS54 Ban Dong Hene WD 3047

NE48-15, J-11D 16-42N, 105-18E  
Elev 500 780x100 Sod 09/27  
CLOSED

LS55 Bolovens XB 6580

ND48-4, K-10A 15-11N, 106-32E  
Elev 3000 900x50 15/33  
CLOSED GROWN OVER

LS56 Moug Chim TG 4443  
 NE48-1, J-11D 19-22N, 102-34E  
 Elev 3700 825x30  
CLOSED GROWN OVER

---

LS57 Phou So/LVI TG 8174  
 NE48-1, J-11D 19-39N, 102-55E  
 Elev 4600 1200x100 Sod 12/30  
 Land 12 TO 30  
RESTRICTED  
Caribou Newly checked out pilots.  
 Closed when wet. MAXLW 26. MAXTOW 24.  
 MAX XWIND 10 kts.

---

LS58 Hua Moug UH 6330  
 NF48-14, J-11A 20-10N, 103-41E  
 Elev 2700 1400x72 10/28  
CLOSED UNF

---

LS59 Phou Kouk UH 8525  
 NF48-14, J-11A 20-07N, 103-54E  
 Elev 4400 800x40 08/26  
CLOSED UNF

---

LS60 Ban Sapi QB 4048  
 NE47-4, J-10C 19-25N, 101-17E  
 Elev 4500 1000x60 Sod 17/35  
CLOSED GROWN OVER

---

LS61 Ban Tha Si UF-7684  
 NE48-6, J-11D 18-50N, 103-49E  
 Elev 2000  
CLOSED UNF

LS62 Ban Hong Sa QB 4581  
 NE47-4, J-10C 19-42N, 101-20E  
 Elev 1800 800x105 Sod 10/28  
OPEN  
Helio, Porter only

---

LS62A Ban Hong Sa QB 4479  
 NE47-4, J-10C 19-41N, 101-20E  
 Elev 2000 1900x45 Grass/Laterite 01/19  
 Land 19 TO 01 Medium Upslope  
RESTRICTED  
Caribou Newly checked out pilots.  
 MAXTOW 28. MAX XWIND 12 kts.

---

LS63 Moug Nham UF 7496  
 NE48-6, J-11D 18-58N, 103-48E  
CLOSED UNF

---

LS64 Ban Don Buong XC 3167  
 ND48-3, K-10A 15-59N, 106-14E  
 Elev 560 1200x50 11/29  
CLOSED UNF

---

LS65 Pha Phai/V UG 1810  
 NE48-1, J-11D 19-05N, 103-16E  
 Elev 3600 600x50 Sod/Clay 11/29  
 Land 29 TO 11, Medium Upslope  
RESTRICTED  
Helio, Porter Newly Checked out pilots.

---

LS66 Ban Na Luang/T TF 6992  
 NE48-5, J-11D 18-54N, 102-49E  
 Elev 1000 650x60 Dirt 10/28  
 Land 10 TO 28 Medium Upslope  
OPEN  
Helio, Porter only

LS67 Phu Hua Moui/L QB 8265

NE47-4, J-10C 19-34N, 101-41E  
Elev 3400 1020x40 16/34  
Land 16 TO 34 Medium Upslope  
RESTRICTED  
Helio, Porter Newly checked out pilots.  
Restricted takeoff weight.

*closed-runway*

LS68 Khang Hong UG 2848

NE48-1, J-11D 19-25N, 103-21E  
Elev 4600 800x35 13/31  
CLOSED UNF

LS69 Ban Xieng Lom/T PB 9274

NE47-4, J-10C 19-39N, 100-50E  
Elev 1900 2300x130 Dirt/Grass 08/26  
RESTRICTED

Caribou MAXLW 28. MAXTOW 28.  
MAX XWIND 15 kts.

C123 Closed when wet. MAXLW 52.5. MAXTOW 46.  
C123K MAXLW 52.5. MAXTOW 50.

*H+P only*

LS70 Na Dao UG 4047

NE48-1, J-11D 19-25N, 103-29E  
Elev 2700 900x45 06/24  
CLOSED UNF

LS71 Phou Nong UG 5855

NE48-2, J-11D 19-29N, 103-39E  
Elev 4600 1170x54 Earth 12/30  
CLOSED UNF

LS72 Tha Tam Bleung/U TG 8827

NE48-1, J-11D 19-13N, 102-59E  
Elev 4500 1000x80 Earth 07/25

CLOSED

*Rest H+P*

LS73 Nam Tang QB 8314

NE47-4, J-10C 19-06N, 101-41E  
Elev 2700 1050x60 17/35  
CLOSED GROWN OVER

LS74 Tham Sorm/V TG 4133

NE48-1, J-11D 19-17N, 103-33E  
Elev 4200 720x35 09/27

Land 27 TO 09, Rolling upslope

RESTRICTED

Helio, Porter Newly checked out pilots.

LS75 Sop Hien TF 7284

NE48-5, J-11D 18-50N, 102-50E  
Elev 3350 670x100 12/30

CLOSED GROWN OVER

LS76 Pha Bong UH 3653

NF48-13, J-11A 20-22N, 103-26E  
Elev 4600 600x50 17/35

CLOSED UNF

LS77 Ban Song Khone WE 2090

NE48-7, J-11D 18-01N, 105-10E  
Elev 1000 500x130 03/21

CLOSED UNF

LS78 Na Poug TG 5548  
 NE48-1, J-11D 19-24N, 102-40E  
CLOSED GROWN OVER

---

LS79 Naw Nuen SG 9535  
 NE48-1, J-11D 19-17N, 102-06E  
CLOSED GROWN OVER

---

LS80 Phu Sang Nao/A TG 8587  
 NE4801, J-11D 19-46N, 102-57E  
CLOSED GROWN OVER  
 UNF

---

LS81 Ban Tham Tat/E UG 9315  
 NE48-2, J-11D 19-08N, 102-59E  
 Elev 4000 630x42 12/30  
CLOSED UNF

---

LS82 Phu Se Bott/U UG 7480  
 NE48-2, J-11D 19-43N, 103-48E  
 Elev 4300 700x40 13/31  
CLOSED GROWN OVER

---

LS83 Ban Nong Dao TF 7014  
 NE48-5, J-11D 18-12N, 102-50E  
 Elev 900x 13/31  
CLOSED GROWN OVER

---

LS84 Ban Keng Sai UG 8322  
 NF48-14, J-11A 20-06N, 103-53E  
CLOSED UNF

LS85 Phu Pha Thi UH 6860  
 NF48-14, J-11A 20-26N, 103-44E  
 Elev 4500 600x50 16/34  
CLOSED UNF

---

LS86 Hong Non UH 8257  
 NF48-14, J-11A 20-24N, 103-52E  
 Elev 4600 700x40 02/20  
CLOSED UNF

---

LS87 Phia Khan VH 0070  
 NF48-14, J-11A 20-31N, 104-03E  
 Elev 3700 900x65 Sod 08/26  
CLOSED UNF

---

LS88 Boun Loum/U UG 2686  
 NE48-1, J-11D 19-46N, 103-20E  
 Elev 5000 800x40 Dirt/Clay 03/21  
 Land 21 TO 03 Rolling Upslope  
RESTRICTED  
Helio, Porter Newly checked out pilots.

---

LS89 Ban Vieng UG 7487  
 NE48-2, J-11D 19-46N, 103-48E  
 Elev 3700 800x75 Sod 16/34  
CLOSED

---

LS90 Tin Bong/E TG 5020  
 NE48-1, J-11D 19-09N, 102-37E  
 Elev 5000 825x100 Dirt 08/26  
OPEN  
Helio, Porter only.

LS91 Moug Tiouen/T VF 3587  
NE48-6, J-11D 18-52N, 104-23E  
Elev 1300 1000x70 Dirt/Sod 12/30  
OPEN  
Helio, Porter only

---

LS92 Sing Ka QB 2692  
NE47-4, J-10C 19-49N, 101, 10E  
Elev 3600 530x62 15/33  
CLOSED UNF

---

LS93 Moug Mounge/T PC 5393  
NF47-15, J-10B 20-44N, 100-29E  
Elev 2000 2030x300 Dirt/Sod 06/24  
Land and TO optional  
RESTRICTED  
Caribou Closed when wet. MAXTOW 26.  
MAXLW 28.5. MAX XWIND 10 kts.

---

LS94 Ban Kha UG 5728  
NE48-2, J-11D 19-15N, 103-39E  
Elev 4300 800x50 14/32  
CLOSED UNF

---

LS95 Ban Peung UG 4422  
NE48-2, J-11D 19-11N, 103-31E  
Elev 4000 1100x64 Dirt 09/27  
CLOSED UNF

---

LS96 Phu Mieng Mane /PI QV 2155  
NE47-12, J-10C 17-40N, 101-05E  
Elev 3700 850x50 Dirt 15/33  
Land 33 TO 15, Medium Upslope  
OPEN  
Helio, Porter only  
UNF

LS97 Ban Pha En TG 5620  
NE48-1, J-11D 19-10N, 102, 41E  
Elev 4250 700x33 Dirt/Clay 07/25  
CLOSED

---

LS98 Long Tieng TG 8214  
NE48-1, J-11D 19-07N, 102-55E  
Elev 3120 2200x100 Laterite 14/32  
Fuel: 115/145, JP-1  
Large aircraft Land 32 TO 14. Medium Upslope.  
Large aircraft 10 kts. XWIND.  
RESTRICTED  
C123 MAXTOW 48.  
C46 MAXTOW 44.

---

LS99 Phu Houot TG 4231  
NE48-1, J-11D 19-16N, 102-32E  
Elev 4400 700x33 Dirt/Sod 09/27  
CLOSED

---

LS100 Ban Beecher TG 4132  
NE48-1, J-11D 19-17N, 102-32E  
Elev 4500 500x40 Dirt/Sod 03/21  
CLOSED

---

LS101 Ban Nong One TG 6532  
NE48-1, J-11D 19-16N, 102-46E  
Elev 3700 700x42 12/30  
CLOSED GROWN OVER

---

LS102 Phu Fa Noi "F" TG 6570  
NE48-1, J-11D 19-37N, 102-46E  
Elev 4100 500x38 Dirt/Sod 03/21  
CLOSED

LS103 Phou Da Pho TG 5243

NE48-1, J-11D 19-22N, 102-38E  
Elev 3700 500x35 Dirt 12/30  
CLOSED

---

LS104 Ban Nam Hin QB 5219

NE47-4, J-10C 19-14N, 101-24E  
Elev 3700 850x65 Sod 04/22  
CLOSED

---

LS105 Phu De Me QB 3544

NE47-4, J-10C 19-25N, 101-15E  
Elev 5800 850x65 18/36  
CLOSED

---

LS106 Nong Sakhe QB 5533

NE47-4, J-10C 19-17N, 101-26E  
Elev 3600 750x35 14/32  
CLOSED

---

LS107 Houei Ma/U UH 6455

NF48-14, J-11A 20-22N, 103-40E  
Elev 4000 820x75 Dirt/Sod 03/21  
Land 03 TO 21 Steep Upslope  
CLOSED UNF

---

LS108 Ban Nam Keng/III UG 7918

NE48-2, J-11D 19-10N, 103-51E  
Elev 4800 600x60 03/21  
CLOSED

---

LS109 Ban Na Woua/T PC7383

NF47-16, J-10B 20-38N, 100-40E  
Elev 3000 700x50 Dirt 12/30  
Land 30 TO 12, Medium Upslope  
RESTRICTED  
Helio, Porter Newly checked out pilots.

---

LS110 Ban Nam Deng/T TG 5513

NE48-1, J-11D 19-11N, 102-40E  
Elev 3800 550x50 09/27  
CLOSED

---

LS111 Houei Kah Moun UH 6868

NF48-14, J-11A 20-31N, 103-44E  
Elev 3850 1050x70 Dirt 10/28  
CLOSED UNF

---

LS112 Sam Sen/V TG 6037

NE48-1, J-11D 19-19N, 102-43E  
Elev 3550 850x40 11/29  
RESTRICTED Land 11 TO 29  
Helio, Porter Newly checked out pilots.

*Closed - runway*

---

LS113 Moung Cha/F UF 0091

NE48-5, J-11D 18-54N, 103-06E  
Elev 3600 1480x85 Dirt/Sod 08/26  
Land 08 TO 26, Medium Upslope  
RESTRICTED  
Caribou MAXTOW (Dry) 27, (Wet) 24.  
Calm wind, MAX XWIND 15 kts.  
Closed when wet.

LS114 Phoung Sam UH 1012

NE48-1, J-11D 20-00N, 103-11E  
Elev 3000 640x75 18/36  
CLOSED GROWN OVER

---

LS115 Phou Kheo UG 3272

NE48-1, J-11D 19-38N, 103-24E  
Elev 5700 400x25 12/30  
CLOSED UNF

---

LS116 New Ban Bouac UG 5831

NE48-2, J-11D 19-16N, 103-39E  
Elev 4300 900x55 07/25  
CLOSED UNF

---

LS117 New Xieng Dat/U TG 6351

NE48-2, J-11D 19-26N, 102-44E  
Elev 2700 1300x90 Clay 06/24  
Land 06 TO 24 Rolling Level  
RESTRICTED  
Caribou Newly checked out pilots. Closed when wet  
MAXLW 26. MAXTOW 24. MAX XWIND 10 kts.

UNF

---

LS118 Ban Nam Thouei/V PC6975

NF47-16, J-10B 20-34N, 100-37E  
Elev 1900 1525x80 06/24  
Land 06 TO 24 Medium Upslope  
Livestock on runway.  
RESTRICTED  
Caribou Closed when wet. No go around.  
MAXTOW 25. MAX XWIND 10 kts.

LS118A Nam Lieu (Nam Yu)/F PC 6575

NF47-16, J-10B 20-34N, 100-35E  
Elev 1900 4360x120 Laterite 07/25  
Fuel: 115/145, JP-1  
Nav aids: NDB 293 NL  
RESTRICTED

Caribou MAX XWIND 10 kts. MAXTOW (Wet) 26.  
Land & TO calm wind only when wet.  
C123 MAXTOW 46. MAX XWIND 10 kts.  
Land & TO 25. Closed when wet.  
C123K MAXLW 54. MAXTOW 52.5  
C46 MAXLW & TOW 42. Closed when wet.

---

LS119 Ban Sa Noi UG 5339

NE48-2, J-11D 19-20N, 103-36E  
Elev 2900 700x 16/34  
CLOSED UNF

---

LS120 Pop's Field TG 9550

NE48-1, J-11D 19-26N, 103-03E  
Elev 3400 1500x 07/25  
CLOSED UNF

---

LS121 Lao Ta TJ 1204

NF48-13, J-11D 20-49N, 102-14E  
Elev 4200 600x55 07/25  
CLOSED UNF

---

LS122 New Hong Non UH 8257

NF48-14, J-11A 20-24N, 103-52E  
Elev 4700 01/19  
CLOSED UNF

LS123 Ban Houei Dioun TG 6948

NE48-1, J-11D 19-24N, 102-48E  
Elev 3650 675/35 07/25  
CLOSED GROWN OVER

LS124 Moung Phieng/P QB 6607

NE47-4, J-10C 19-03N, 101-32E  
Elev 1200 1200x66 16/34  
Land 34 TO 16. 300' overrun at north end,  
overrun soft. Trees at north end of runway.  
CLOSED

LS125 Nam Bu/T PD 9908

NF47-16, J-10B 20-52N, 100-55E  
Elev 3850 600x45 16/34  
Land 34 TO 16 Medium Upslope  
RESTRICTED  
Helio, Porter Newly checked out pilots.

LS126 New San Soak/E VF 5959

NE48-6, J-11D 18-37N, 104-36E  
Elev 3000 885x70 Dirt/Grass 06/24  
Land Optional TO 06 Rolling Level  
CLOSED UNF

LS127 Houei Sa An/AI UG 4191

NE48-1, J-11D 19-49N, 103-29E  
Elev 3600 06/24  
CLOSED

UNF

LS128 Moung Khao UG 4289

NE48-2, J-11D 19-48N, 103-30E  
Elev  
CLOSED

UNF

LS129 Borikhane UF 6653

NE48-6, J-11D 18-34N, 103-44E  
Elev 400 900x50 14/32  
Land 14 TO 32. Limited use, no windsock or  
runway markers.

CLOSED UNF

closed-runway

LS130 La Ta Sin XB 7364

ND48-4, K-10A 15-03N, 106-36E  
Elev 2400 1050x195 13/31  
Land 13 TO 31 Medium Upslope  
RESTRICTED  
Caribou Newly checked out pilots. Emergency  
use only until runway construction completed.  
MAXLW 26. MAXTOW 22. MAX XWIND 5 kts.

LS131 Mok Lok TH 3671

NF48-13, J-11A 20-31N, 102-26E  
Elev 2850 600x40 14/32  
CLOSED UNF

LS132 Long Pot TG 3637

NE48-1, J-11D 19-19N, 102-30E  
Elev  
CLOSED

LS133 Phong Hong TF 2747

NE48-5, J-11D 18-30N, 102-25E  
Elev 750 2310x80 Sod/Laterite 02/20  
Trees bordering runway, 02 end.  
RESTRICTED  
Caribou Land 20 TO 02. MAX XWIND 10 kts.

LS134 Ban Nong Boua XC 6733

ND48-4, K-10A 15-40N, 106-33E  
Elev 700 1180x60 Sand 10/28

Trees close to both sides of runway.

RESTRICTED

Caribou Newly checked out pilots. Closed when  
wet. MAXLW 26. MAXTOW 24.  
MAX XWIND 10 kts.

LS135 Ban Vieng QC 1889

NF47-16, J-10B 20-42N, 101-05E  
Elev 2400 1940x100 Dirt 11/29

750' runway unusable, under construction for  
larger aircraft.

RESTRICTED

Caribou Newly checked out pilots.  
MAXLW 28, MAXTOW 26.

LS136 Ba Phu Lun QC 2283

NF47-16, J-10B 20-38N, 101-08E  
Elev

CLOSED

LS137 Mak Phout TH 1876

NF48-13, J-11A 20-34N, 102-18E  
Elev 3700 975x60 02/20

CLOSED UNF

LS138 Ban Chuk Chung TJ 2302

NF48-13, J-11A 20-48N, 102-21E  
Elev 2900 650x50 03/21

CLOSED UNF

*Post - HHP*

LS139 Keng Kok WD 2118

NE48-15, J-11D 16-27N, 105-11E  
Elev 560 1300x65 Gravel 11/29

Avoid gravel areas during runup.

RESTRICTED

Caribou Newly checked out pilots.  
MAXLW 26. MAXTOW 24. MAX XWIND 10 kts.

LS140 Phou Houang UG 0729

NE48-1, J-11D 19-15N, 103-10E  
Elev 5200 475x45 16/34

CLOSED UNF

LS141 Grove Jones VE 4864

NE48-2, J-11D 19-46N, 104-31E  
Elev 600 1500x30 14/32

CLOSED

LS141A Grove Jones 2 VE 2794

NE48-6, J-11D 18-03N, 104-19E  
Elev 520 2525x140 Gravel/Laterite 15/33

Runway part of highway, watch for traffic.

Rolling Medium Upslope.

RESTRICTED

Caribou Land 15 TO 33. MAXLW & TOW (Wet) 26.  
MAX XWIND 15 kts.

C123 MAXTOW 48.

C123K MAXLW 54. MAXTOW 52.5

LS142 Phou Pang Sang/HL QC 2878

NF47-16, J-10B 20-35N, 101-11E  
Elev 3200 1400x40 09/27

Land 09 TO 27. Medium Upslope

OPEN

Helio, Porter only

LS143 Ban Nam Dua VF 1812  
NE48-6, J-11D 18-11N, 104-13E  
Elev 600 1200x80 Dirt/Sod 18/36  
Filled in ditch in middle of runway, soft when wet.  
RESTRICTED  
Caribou Newly checked out pilots.  
Closed when wet. MAXLW 26. MAXTOW 24.  
MAX XWIND 10 kts.

LS144 Ban Da Bom VF 5500  
NE48-6, J-11D 18-05N, 104-35E  
Elev 650 1050x95 03/21  
CLOSED

LS145 Tong Prang/V QC 4674  
NF47-16, J-10B 20-33N, 101-21E  
Elev 2400 650x50  
CLOSED

LS146 Phou Nam Nhiou/L QB 5406  
NE47-4, J-10C 19-02N, 101-25E  
Elev 2300 700x30 04/22  
CLOSED

LS147 Ban Houei Lao PB 5986  
NE47-4, J-10C 19-46N, 100-31E  
Elev 1700 780x65 08/26  
CLOSED UNF

LS148 Ban Nou Kha Chok/T PC 7706  
NE47-4, J-10C 19-56N, 100-41E  
Elev 2900 750x75 15/33  
Land 15 TO 33. Steep Upslope. First 100' of  
runway very steep.  
CLOSED UNF

LS149 Ban Nam Nhion/L PC 3956  
NF47-15, J-10B 20-24N, 100-20E  
Elev 1600 970x90 Dirt 17/35  
CLOSED

LS150 Ban Nam Kueung/T PC 3255  
NF47-15, J-10B 20-24N, 100-16E  
Elev 1600 1450x115 Clay 03/21  
RESTRICTED  
Caribou Newly checked out pilots.  
Closed when wet. MAXLW 28. MAXTOW 26.  
MAX XWIND 10 kts.

LS151 Ban Sa Phout/T QC 3969  
NF47-16, J-10B 20-30N, 101-17E  
Elev 3300 570x65 08/26  
CLOSED

LS152 Vien Pou Kha/F/T QC 1488  
NF47-16, J-10B 20-41N, 101-03E  
Elev 2000 1800x50 03/21  
CLOSED

LS153 Moug Kassy/T TG 1130  
NE48-1, J-11D 19-15N, 102-15E  
Elev 1300 1113x75 Sod 16/34  
RESTRICTED  
Caribou Closed when wet.  
*closed*

LS154 Nong Pet/T SF 9879  
NE48-5, J-11D 18-47N, 102-08E  
Elev 900 900x100 Sod 06/24  
OPEN  
Hello, Porter only

LS155 Phia Chan/P PB 8762

NE47-4, J-10C 10-33N, 100-47E  
Elev 2050 1050x75 Dirt 15/33  
Land 15 TO 33  
OPEN  
Helio, Porter only

---

LS156 Phou Soung/T TG 3756

NE48-1, J-11D 19-28N, 102-30E  
Elev 4300 675x35 Dirt 11/29  
Medium Upslope  
RESTRICTED  
Helio, Porter Newly checked out pilots

---

UNF

---

LS157 Moang Soum TF 4973

NE48-5, J-11D 18-45N, 102-37E  
Elev 900 1800x72 Laterite 10/28  
Land 10 TO 28  
RESTRICTED  
Caribou MAXLW 28. MAXTOW 26.

---

LS158 Moung Met RA 1085

NE48-5, J-11D 18-50N, 102-51E  
Elev 900 1000x65 Dirt 06/24  
Land 06 TO 24 Medium Upslope  
OPEN  
Helio, Porter only

---

LS159 La Khong Pheng WC 6158

NE48-3, K-10A 15-54N, 105-34E  
Elev 500 1300/75 Clay/Sand 16/34  
RESTRICTED  
Caribou Newly checked out pilots.  
Closed when wet. MAXLW 26. MAXTOW 24.  
MAX XWIND 10 kts.

LS160 Doi Seang RD 0935

NF47-12, J-10B 21-05N, 101-59E  
Elev 4100 1200x100 18/36  
CLOSED UNF

---

LS161 Ban Nam Thao TG 6529

NE48-1, J-11D 19-15N, 102-46E  
Elev 3625 630x55 Dirt/Sod 12/30  
Land 30 TO 12. Medium Upslope  
RESTRICTED  
Helio, Porter Newly checked out pilots.

---

LS162 Sen Sai QC 1653

NF47-16, J-10B 20-22N, 101-04E  
Elev 4200 520x60 15/33  
CLOSED UNF

---

LS163 Ban Donge/F SF 9868

NE48-5, J-11D 18-41N, 102-08E  
Elev 700 1400x75 Dirt 18/36  
Land 18 TO 36  
RESTRICTED  
Caribou Newly checked out pilots.  
MAXLW 28. MAXTOW 25. Closed when wet.

---

LS164 Houei Soi XB 6853

ND48-8, K-10A 14-57N, 106-34E  
Elev 2900 1800x60 Sand/Sod 16/34  
RESTRICTED  
Caribou Closed when wet. MAXTOW 26.  
MAX XWIND 15 kts.

LS165 Ban Nam Tieng XB 8359  
ND 48-4, K-10A 15-00N, 106-12E  
Elev 3300 1600x60 Dirt 13/31  
Land 31 TO 13 Medium Upslope  
RESTRICTED  
Caribou Closed when wet.  
MAXLW 28.5 MAXTOW 26.

---

LS166 Phou Kham Phouk XB 8851  
ND48-8, K-10A 14-56N, 106-45E  
Elev 3950 1500x115 Dirt/Sod 18/36  
Land 18 TO 36. Rolling Steep Upslope.  
RESTRICTED  
Caribou Closed when wet. MAXLW 28.  
MAXTOW 26. MAX XWIND 10 kts.

---

LS167 Tang Hung XB 6877  
ND48-8, K-10A 15-10N, 103-34E  
Elev 2950 1050x70 Sod 08/26  
RESTRICTED  
Helio, Porter when wet for newly checked  
out pilots.

---

LS168 Moug Ngeum/LI QC 1578  
NF47-16, J-10B 20-35N, 101-04E  
Elev 2300 1340x120 Sod 03/21  
CLOSED GROWN OVER

---

LS169 Ban Pha Thong TJ 3409  
NF48-13, J-11A 20-51N, 102-26E  
Elev 3500 725x75 Sod 06/24  
CLOSED UNF

LS170 Pha Langmou/F/L TG 2967  
NE48-1, J-11D 19-35N, 102-25E  
Elev 5500 670x55 Dirt 08/25  
Land 08 TO optional Rolling Upslope  
OPEN  
Porter only

---

LS171 Ban Khok Mai XC 5839  
ND48-3, K-10A 14-49N, 106-28E  
Elev 600 710x75 Grass 10/28  
Medium Upslope  
OPEN  
Helio, Porter only.

---

LS172 Long Keo XB 7940  
ND48-8, K-10A 14-50N, 106-40E  
Elev 3100 1050x70 Dirt 10/28  
RESTRICTED  
Caribou Land 10 TO 28. Newly checked out pilots.  
MAXLW 26. MAXTOW 22. MAX XWIND 5 kts.  
Closed when wet.

---

LS173 Tong Hang/L TF 9183  
NE48-5, J-11D 18-50N, 103-01E  
Elev 3200 850x90 Grass/Dirt 07/25  
Land 25 TO 07 Portion of runway is rough  
rice paddy.  
RESTRICTED  
Helio, Porter when wet.

---

LS174 Boum Lao QC 5021  
NF47-16, J-10B 20-04N, 101-24E  
Elev 1500 850x35 11/29  
CLOSED UNF

LS175 Ban Saphat

XC 0435

ND48-3, K-10A  
Elev 400 1450x100  
CLOSED

15-42N, 105-58E  
18/36

LS176 Nam Thuam

TH 2568

NF48-13, J-11A  
Elev 1300 1200x75  
CLOSED UNF

20-29N, 102-22E  
09/27

LS177 Ban Moug/V

PB 6077

NE47-4, J-10C  
Elev 1400 600x60  
Land 27 TO 09  
RESTRICTED  
Helio, Porter only

19-41N, 100-32E  
09/27

Restrict TO weight

LS178 Phou Saly/K

TH 9363

NF48-13, J-11A  
Elev 3200 750x45 Dirt  
Land 13 TO 31. No go around. Tricky winds.

20-27N, 103-01E  
13/31

RESTRICTED  
Helio, Porter Newly checked out pilots.  
Restricted takeoff weight.

LS179 Nhot Phat

UH 6743

NF48-14, J-11A  
Elev 4000 1100x60  
CLOSED UNF

20-17N, 103-43E  
09/27

LS180 New Paksong

XB 3279

ND48-4, L-10A  
Elev 4600 1500x180  
TO 30  
OPEN  
Helio, Porter only

15-11N, 106-14E  
12/30

LS181 Na Xieng

UG 5348

NE48-2, J-11D  
Elev 4000 750x55 Dirt  
CLOSED

19-25N, 103-36E  
12/30

UNF

LS182 Moug Mo

UG 9109

NE48-2, J-11D  
Elev 1400 1680x65 Grass  
CLOSED UNF

19-04N, 103-58E  
14/32

LS183 Ban Nong Bok

VD 7988

NE-48-10, J-11D  
Elev 640 1400x40  
OPEN  
Helio, Porter only

17-05N, 104-48E  
02/20

LS184 Houei Tong Ko/T

UH 1853

NF48-13, J-11A  
Elev 4500 1110x46  
Land 31 TO 13 Rolling Upslope  
RESTRICTED  
Helio, Porter Newly checked out pilots.

20-22N, 103-15E  
13/31

- LS185 Phou Tia UH 4364  
NF48-13, J-11A 20-28N, 103-30E  
Elev 4500 1250x70 02/20  
CLOSED UNF
- 
- LS186 Tong Too TH 0567  
NF48-13, J-11A 20-29N, 102-10E  
Elev 4000 1000x40 Dirt/Rock 02/20  
CLOSED UNF
- 
- LS187 Ban "Y" TJ 4716  
NF48-13, J-11A 20-55N, 102-36E  
Elev 2300 750x50 05/23  
CLOSED UNF
- 
- LS188 Xing Than TJ 6324  
NF48-13, J-11A 21-00N, 102-43E  
Elev 2300 675x65 05/23  
CLOSED UNF
- 
- LS189 Ban Houei Sane XD 6536  
NE48-16, J-11D 16-36N, 106-32E  
Elev 480 3000x100 09/27  
CLOSED UNF
- 
- LS190 Ban La Tee XB 9168  
ND-48-4, K-10A 15-05N, 106-42E  
Elev 2800 2636x80 Mixed laterite & clay 16/34  
Navoids: NDB 405 NH  
Land 16 TO 34  
Trees and gradually rising terrain of SE end of  
runway  
RESTRICTED  
Caribou Caution when wet. MAXL/TOW 26 with  
calm wind condition only. MAX XWIND 10 kts.  
C123K MAXLW 55. MAXTOW 52.5  
Closed when wet.

- LS191 Thong Kheun/F TF 9586  
NE48-5, J-11D 18-51N, 103-03E  
Elev 3200 900x60 Dirt 08/26  
Rolling Upslope  
OPEN  
~~Helio, Porter only~~  
*closed - Runway*
- 
- LS192 Khieu Manang/V UF 2497  
NE48-5, J-11D 18-57N, 103-20E  
Elev 2930 900x60 08/26  
Land 08 TO 26  
OPEN  
Helio, Porter only
- 
- LS193 Mok Plai TH 1889  
NF48-13, J-11A 20-41N, 102-17E  
Elev 4000 1200x40 Grass/Dirt 03/21  
CLOSED UNF
- 
- LS194 Ban Bo Mei QD 0161  
NF47-16, J-10B 11-20N, 100-55E  
Elev 3100 700x65 11/29  
CLOSED

LS195 Muang Kout/TN UH 3044

NF48-13, J-11A 20-17N, 103-22E  
Elev 3600 1000x75 14/32  
Land 14 TO 32. Rolling Upslope  
CLOSED UNF

LS196 Huie Thong/L TH 8750

NF48-13, J-11A 20-25N, 102-58E  
Elev 3600 900x48 18/36  
Land 36 TO 18. Steep Upslope. Expect down-  
draft w/east wind and up-draft w/west wind.  
RESTRICTED  
Helio, Porter Newly checked out pilots

LS197 Phou Vieng/H TG 4958

NE48-1, J-11D 19-28N, 102-36E  
Elev 4200 850x45 11/29  
Land 29 TO 11. Rolling Medium Upslope  
Runway irregular in slope, direction & width.  
RESTRICTED  
Helio, Porter Newly checked out pilots

LS198 Houei Hok UH 6561

NF48-14, J-11A 20-27N, 103-42E  
Elev 3000 900x45 09/27  
CLOSED UNF

LS199 Nam Song/TI UG 7621

NE48-2, J-11D 19-11N, 103-49E  
Elev 5200 900x60 Dirt 17/35  
CLOSED

LS200 Houei Hong/I TG 5568

NE48-1, J-11D 19-36N, 102-40E  
Elev 2400 860x50 03/21  
Land 21 TO 03  
RESTRICTED  
Helio, Porter Newly checked out pilots.

LS201 Sam Song Hong/I UG 8483

NE48-2, J-11D 19-44N, 103-54E  
Elev 3300 900x70 Sandy Loam 17/35.  
Land 17 TO 35  
RESTRICTED  
Helio, Porter Newly checked out pilots when wet.

LS202 Thung Peeut/T VF 0095

NE48-2, J-11D 19-57N, 104-03E  
Elev 2900 700x40 11/29  
Land 11 TO 29 Medium Upslope  
RESTRICTED  
Helio, Porter Newly checked out pilots

LS203 Nam Bac TH 3583

NF48-13, J-11A 20-38N, 102-27E  
Elev 1150 2600x80 09/27  
CLOSED UNF

LS204 Khang Kho/TH UG 0524

NE48-1, J-11D 19-17N, 103-09E  
Elev 4800 658x48 03/21  
Land 03 TO 21 Steep Upslope  
CLOSED

LS205 Pha Hang/F UH 7546  
NF48-14, J-11A 20-18N, 103-48E  
Elev 4800 750x50 02/20  
CLOSED UNF

LS206 Houei Sang/H UG 8192  
NE48-2, J-11D 19-50N, 103-52E  
Elev 2900 660x50 10/28  
Land 10 TO 28 Medium Upslope  
RESTRICTED  
Helio, Porter Newly checked out pilots

LS207 Nam Moh/L TF 8287  
NE48-5, J-11D 18-52N, 102-56E  
Elev 1500 960x108 Sandy Loam 11/29  
Land 11 TO 29 Medium Upslope  
OPEN  
Helio, Porter only

*Open, H+P*  
~~Closed Runway~~

LS208 Ban Nam Xao/III UG 7718  
NE48-2, J-11D 19-10N, 103-50E  
Elev 4700 870x96 Loam/Rock 04/22  
Land 22 TO 04 Medium Upslope  
OPEN  
Helio, Porter only

LS209 Ban Nong Tong/MF QB 1299  
NE47-4, J-10C 19-54N, 101-02E  
Elev 3000 530x40 Grass 11/29  
Land 11 TO 29 Medium Upslope  
RESTRICTED  
Helio, Porter Newly checked out pilots.

LS210 Thateng XC 4807  
ND48-3, K-10A 15-26N, 106-23E  
Elev 2700 1500x50 Crushed Rock 17/35  
OPEN  
Helio, Porter only

LS211 Phone Sai/TI TF 6299  
NE48-5, J-11D 18-58N, 102-45E  
Elev 1000 1080x40 16/34  
Medium Upslope  
OPEN  
Helio, Porter only

LS212 Phu Moun/H UG 4590  
NE48-5, J-11D 18-54N, 103-32E  
Elev 3100 670x50 17/35  
CLOSED UNF

LS213 Pha Hong/P TG 4374  
NE48-1, J-11D 19-39N, 102-33E  
Elev 4100 960x48 Sandy/Loam 14/32  
Land 32 TO 14 Steep Upslope  
RESTRICTED  
Helio, Porter Newly checked out pilots.

LS214 Ban Nongla UG 6042  
NE48-2, J-11D 19-22N, 103-40E  
Elev 3600 800x40 18/36  
CLOSED UNF

LS215 Houei Hinsu/T UH 4457  
NF48-14, J-11A 20-24N, 103-30E  
Elev 4700 600x60 Sod 15/33  
Land 33 TO 15 Rolling Upslope  
CLOSED UNF